

CENTRAL PUBLIC WORKS DEPARTMENT

?????? ?????? ?????

Office of the Executive Engineer, Project Division

NOTICE INVITING e-TENDER No. CE/ELE/41/2026-27

Name of work: Supply, installation, testing and commissioning of LT electrical distribution system.

Estimated cost put to tender: Rs. 283,97,000/-

Earnest Money Deposit: Rs. 9,70,000/-

Period of completion: 18 months

Last date of submission: 26.10.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.
2. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.
3. Conditional bids will be summarily rejected.
4. The bid shall remain valid for 90 days from the date of opening of the technical bid.

SPECIAL CONDITIONS OF CONTRACT

1. Liquidated damages at 0.5 % per week of delay shall be levied, subject to a maximum of 10 % of the contract value.
2. Income tax and GST shall be deducted at source as applicable.
3. Payment shall be made within 30 days of receipt of bills duly certified by the Engineer-in-charge.

SCOPE OF WORK

This specification covers supply, installation, testing and commissioning of It

Signature of Bidder

electrical distribution system complete in all respects.

SITE CONDITIONS

- (a) The equipment shall be designed for a maximum ambient temperature of 40°C.
- (b) Relative humidity at site may reach 95 %.
- (c) The installation is at an altitude of 2600 m above mean sea level.

PART D — MAIN LT PANEL

- (a) The LT panel shall conform to IS/IEC 61439-1:2020 and IS/IEC 61439-2:2020.
- (b) The panel shall be cubicle type, floor mounted, fabricated from CRCA sheet steel of 2mm thickness.
- (c) The rated operational voltage shall be 415 V, 3 phase, 4 wire, 50 Hz.
- (d) Main busbars shall be of electrolytic grade aluminium rated for 1600A continuous current.
- (e) The busbars and panel shall withstand a short circuit current of 50 kA for 1 second.
- (f) The degree of protection of the panel enclosure shall be IP54.
- (g) The switchboard shall have Form 3b internal separation.
- (h) Incomers shall be 1600A, 4 pole, electrically operated air circuit breakers conforming to IS/IEC 60947-2:2003.
- (i) Outgoing feeders shall be MCCBs with ultimate breaking capacity of 36 kA.
- (j) Multifunction meters of accuracy class 0.5 shall be provided on each incomer.

GUARANTEED TECHNICAL PARTICULARS — LT PANEL

Rated voltage: 415 V

Rated current of main busbar: 1600A

Short time current rating: 50 kA for 1 s

Degree of protection: IP54

Make and type: (to be furnished by the bidder)

Signature of Bidder

PART E — LT POWER AND CONTROL CABLES

- (a) Power cables shall be 1.1 kV grade, aluminium conductor, XLPE insulated, armoured and PVC sheathed, conforming to IS 7098 (Part 1):1988.
- (b) The cables shall be suitable for a maximum continuous conductor temperature of 90°C.
- (c) Control cables shall be PVC insulated, copper conductor of 2.5 sq mm, 1.1 kV grade, conforming to IS 1554 (Part 1).
- (d) Conductors shall be stranded, class 2, conforming to IS 8130.
- (e) Cables shall be laid in RCC trenches or on perforated cable trays as shown in the drawings.
- (f) Cable ends shall be terminated using double compression glands and crimped lugs.
- (g) Each drum shall be marked with the manufacturer's name, size, voltage grade and year of manufacture.

6 TESTS AND INSPECTION

- (a) Routine verification of each assembly shall be carried out in accordance with IS/IEC 61439-1.
- (b) Routine test certificates of cables shall be furnished with each consignment.
- (c) The equipment shall be inspected by the Engineer-in-charge at the manufacturer's works before dispatch.

7 DOCUMENTATION, WARRANTY AND TRAINING

- (a) The contractor shall submit detailed shop drawings for approval within 21 days of award of work.
- (b) Three sets of operation and maintenance manuals shall be handed over on completion.
- (c) The complete installation shall be guaranteed against defective design, material and workmanship for a period of 12 months from the date of handing over.
- (d) The contractor shall train the Department's operating staff in operation and routine

Signature of Bidder

maintenance.

BILL OF QUANTITIES

Sl. No. | Description | Unit | Qty

- 1 | Main LT panel as per specification | Set | 1
- 2 | Sub-distribution board, 12 way TPN | No. | 8
- 3 | 3.5C x 300 sq mm XLPE armoured cable | m | 350
- 4 | Cable tray 300 mm wide | m | 120

APPROVED MAKES OF MATERIALS

LT panel builder: as per approved list; ACB/MCCB: L&T / Siemens / Schneider / ABB

Cables: Polycab / KEI / Havells / RR Kabel

Note: Drawings are indicative only and shall be verified at site.

Note: Quantities are approximate and may vary during execution.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 4 of 4