

JAL NIGAM

????????? ???????

Office of the Executive Engineer, Division No. 2

NOTICE INVITING e-TENDER No. EE/WS/33/2026-27

Name of work: Design, supply and commissioning of raw water pumping machinery.

Estimated cost put to tender: Rs. 148,59,000/-

Earnest Money Deposit: Rs. 6,48,000/-

Period of completion: 18 months

Last date of submission: 17.11.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. The bid shall remain valid for 90 days from the date of opening of the technical bid.
2. Conditional bids will be summarily rejected.
3. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
4. Bids received after the due date and time shall not be considered.
5. The Department reserves the right to accept or reject any bid without assigning any reason.
6. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.

COMMERCIAL TERMS AND CONDITIONS

1. The contractor shall indemnify the Department against all claims arising out of the work.
2. Liquidated damages at 0.5 % per week of delay shall be levied, subject to a maximum of 10 % of the contract value.
3. All disputes shall be subject to arbitration under the Arbitration and Conciliation Act, 1996.
4. Rates quoted shall be inclusive of all taxes, freight, insurance and transit risks.

Signature of Bidder

Page 1 of 4

SCOPE OF WORK

This specification covers design, supply and commissioning of raw water pumping machinery complete in all respects.

3 TECHNICAL SPECIFICATION — HORIZONTAL CENTRIFUGAL PUMPS

1. Pumps shall conform to IS 1520:1980.
2. Each pump shall deliver 250 m³/h against a total head of 45 m. The pump efficiency at the duty point shall not be less than 78%.
3. Casing shall be of cast iron and impeller shall be of bronze.
4. Noise level at 1 m from the pumpset shall not exceed 85 dB(A).

PUMP DATA SHEET

Discharge: 250 m³/h

Total head: 45 m

Make and type: (to be furnished by the bidder)

4 TECHNICAL SPECIFICATION — DRIVE MOTORS

1. Motors shall be squirrel cage induction motors conforming to IS 325:1996.
2. The rated output of the motor shall be 37kW.
3. Motors shall be suitable for 415V $\pm$ 15%, 50Hz $\pm$ 5%, 3 phase supply.
4. Motors shall be energy efficient.
5. Motors shall have class F insulation with temperature rise limited to class B and shall be suitable for S1 duty.
6. Synchronous speed of the motor shall be 1500 RPM.

5 TECHNICAL SPECIFICATION — LT POWER AND CONTROL CABLES

1. Power cables shall be 11 kV grade, aluminium conductor, XLPE insulated, armoured and PVC sheathed, conforming to IS 7098 (Part 1):1988.

Signature of Bidder

2. The main feeder cable shall be 3.5 core 300 sq.mm.
3. The cables shall be suitable for a maximum continuous conductor temperature of 90 deg C. Control cables shall be PVC insulated, copper conductor of 2.5 sq.mm, 1.1 kV grade, conforming to IS 1554 (Part 1).
4. Conductors shall be stranded, class 2, conforming to IS 8130. Cables shall be laid in RCC trenches or on perforated cable trays as shown in the drawings.
5. Cable ends shall be terminated using double compression glands and crimped lugs.
6. Each drum shall be marked with the manufacturer's name, size, voltage grade and year of manufacture.

SECTION 6: TESTING, INSPECTION AND CERTIFICATION

1. Pumps shall be tested at the works in accordance with IS 9137. Pumps shall bear the ISI mark.
2. Routine tests on motors shall be carried out as per IS 4029.
3. Motors shall bear the ISI mark.
4. Cables shall be tested in accordance with IS 10810.
5. Routine test certificates of cables shall be furnished with each consignment. The equipment shall be inspected by the Engineer-in-charge at the manufacturer's works before dispatch.

7 DOCUMENTATION, WARRANTY AND TRAINING

1. The contractor shall submit detailed shop drawings for approval within 21 days of award of work.
2. Three sets of operation and maintenance manuals shall be handed over on completion.
3. The complete installation shall be guaranteed against defective design, material and workmanship for a period of 12 months from the date of handing over.
4. The contractor shall train the Department's operating staff in operation and routine maintenance.

Signature of Bidder

SCHEDULE OF QUANTITIES

Sl. No. | Description | Unit | Qty

- 1 | Horizontal centrifugal pumpset 250 m³/hr at 45 m | Set | 3
- 2 | Squirrel cage induction motor 37 kW, 1500 rpm | No. | 3
- 3 | 3.5C x 300 sq mm XLPE armoured cable | m | 350
- 4 | Cable tray 300 mm wide | m | 120

APPROVED MAKES OF MATERIALS

Pumps: Kirloskar Brothers / KSB / Mather & Platt

Motors: ABB / Siemens / Crompton Greaves / Kirloskar

Cables: Polycab / KEI / Havells / RR Kabel

Note: Drawings are indicative only and shall be verified at site.

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 4 of 4