

PUBLIC HEALTH ENGINEERING DEPARTMENT

Office of the Executive Engineer, Circle I

NOTICE INVITING e-TENDER No. EE/CIV/19/2026-27

Name of work: Supply and installation of borewell submersible pumpsets and water quality testing.

Estimated cost put to tender: Rs. 244,99,000/-

Earnest Money Deposit: Rs. 4,51,000/-

Period of completion: 9 months

Last date of submission: 11.10.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. The Department reserves the right to accept or reject any bid without assigning any reason.
2. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.
3. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.
4. The bid shall remain valid for 90 days from the date of opening of the technical bid.

COMMERCIAL TERMS AND CONDITIONS

1. Income tax and GST shall be deducted at source as applicable.
2. Liquidated damages at 0.5 % per week of delay shall be levied, subject to a maximum of 10 % of the contract value.
3. All disputes shall be subject to arbitration under the Arbitration and Conciliation Act, 1996.

SCOPE OF WORK

Signature of Bidder

This specification covers supply and installation of borewell submersible pumpsets and water quality testing complete in all respects.

3 TECHNICAL SPECIFICATION — BOREWELL SUBMERSIBLE PUMPSETS

- (a) Borewell submersible pumpsets shall conform to IS 8034:2018.
- (b) Each pumpset shall deliver 18 m³/hr against a total head of 90 m.
- (c) Motors shall be water filled, wet type, conforming to IS 9283:2013.
- (d) Submersible flat cables shall be 3 core, 6 mm², copper conductor, PVC insulated, conforming to IS 694:2010 and tested as per IS 10810. Each pumpset shall be provided with an automatic starter with single phasing preventer and dry run protection.

PART D — TREATED WATER QUALITY

- (a) Treated water supplied shall conform to IS 10500:2012.
- (b) pH of treated water shall be between 6.5 and 8.5.
- (c) Total dissolved solids shall not exceed 500 mg/l.
- (d) Turbidity shall not be more than 5 NTU.
- (e) Fluoride shall not exceed 1.0 mg/l.
- (f) Nitrate shall not exceed 45 mg/l. Arsenic shall not exceed 0.01 mg/l.
- (g) Total hardness as CaCO₃ shall not exceed 200 mg/l.
- (h) E. coli shall not be detectable in any 100 ml sample.

5 TESTS AND INSPECTION

- (a) Pumpsets shall bear the BIS Standard Mark.
- (b) Water samples shall be tested in a NABL accredited laboratory as per IS 3025 and IS 1622.
- (c) The equipment shall be inspected by the Engineer-in-charge at the manufacturer's works before dispatch.

Signature of Bidder

6 DOCUMENTATION, WARRANTY AND TRAINING

- (a) Test reports shall be submitted to the Engineer-in-charge for each source. The contractor shall submit detailed shop drawings for approval within 21 days of award of work.
- (b) Three sets of operation and maintenance manuals shall be handed over on completion.
- (c) The complete installation shall be guaranteed against defective design, material and workmanship for a period of 12 months from the date of handing over.
- (d) The contractor shall train the Department's operating staff in operation and routine maintenance.

SCHEDULE OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | Submersible pumpset 18 m³/hr at 90 m head | Set | 12

2 | Water quality testing (complete set of parameters) | Sample | 48

LIST OF APPROVED MAKES

Submersible pumps: CRI / Kirloskar / Texmo

Testing laboratory: NABL accredited

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Note: Quantities are approximate and may vary during execution.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 3 of 4

