

VIDYUT VITRAN NIGAM LIMITED

Office of the Executive Engineer, Project Division

NOTICE INVITING e-TENDER No. EE/WS/96/2026-27

Name of work: Procurement of distribution transformers and LT cables.

Estimated cost put to tender: Rs. 219,47,000/-

Earnest Money Deposit: Rs. 6,78,000/-

Period of completion: 9 months

Last date of submission: 20.11.2026 up to 15:00 hrs

SECTION I — INSTRUCTIONS TO TENDERERS

1. Conditional bids will be summarily rejected.
2. The tender documents may be downloaded from the e-procurement portal of the Government.
3. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.
4. The successful bidder shall furnish a performance guarantee of 5 % of the contract value within 15 days.
5. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.

SCOPE OF WORK

This specification covers procurement of distribution transformers and It cables complete in all respects.

SECTION 3: DISTRIBUTION TRANSFORMERS

- The transformers shall conform to IS 1180 (Part 1):2014.
- Rating: 630 kVA, 11/0.433 kV, Dyn11 vector group.
- The transformers shall meet energy efficiency level 2 as specified in IS 1180 (Part

Signature of Bidder

Page 1 of 3

1).

- Type: outdoor, oil immersed, ONAN cooled, copper wound.
- Temperature rise of top oil shall not exceed 35 °C over an ambient of 50 °C.
- The tank shall be of welded mild steel and painted with epoxy based paint.

SECTION 4: LT POWER AND CONTROL CABLES

- Power cables shall be 1.1 kV grade, aluminium conductor, XLPE insulated, armoured and PVC sheathed, conforming to IS 7098 (Part 1):1988.
- The cables shall be suitable for a maximum continuous conductor temperature of 90 °C.
- Control cables shall be PVC insulated, copper conductor of 2.5 sq mm, 1.1 kV grade, conforming to IS 1554 (Part 1).
- Conductors shall be stranded, class 2, conforming to IS 8130.
- Cables shall be laid in RCC trenches or on perforated cable trays as shown in the drawings.
- Cable ends shall be terminated using double compression glands and crimped lugs.
- Each drum shall be marked with the manufacturer's name, size, voltage grade and year of manufacture.

5 TESTS AND INSPECTION

- All routine tests shall be carried out on each transformer as per IS 2026 (Part 1):1977.
- Type test reports of the offered design from a NABL accredited laboratory shall be submitted with the bid.
- The equipment shall be inspected by the Engineer-in-charge at the manufacturer's works before dispatch.

6 DOCUMENTATION, WARRANTY AND TRAINING

- The contractor shall submit detailed shop drawings for approval within 21 days of

Signature of Bidder

award of work.

- Three sets of operation and maintenance manuals shall be handed over on completion.
- The complete installation shall be guaranteed against defective design, material and workmanship for a period of 12 months from the date of handing over.
- The contractor shall train the Department's operating staff in operation and routine maintenance.

BILL OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | 630 kVA 11/0.433 kV distribution transformer | No. | 4

2 | 3.5C x 300 sq mm XLPE armoured cable | m | 350

3 | Cable tray 300 mm wide | m | 120

LIST OF APPROVED MAKES

Transformers: as per approved vendor list of the utility

Cables: Polycab / KEI / Havells / RR Kabel

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Note: Drawings are indicative only and shall be verified at site.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 3 of 3