

WATER SUPPLY AND DRAINAGE BOARD

??? ?????? ??????

Office of the Executive Engineer, Circle I

NOTICE INVITING e-TENDER No. CE/MM/94/2026-27

Name of work: Construction of RCC elevated service reservoir.

Estimated cost put to tender: Rs. 254,89,000/-

Earnest Money Deposit: Rs. 9,24,000/-

Period of completion: 6 months

Last date of submission: 23.10.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. The tender documents may be downloaded from the e-procurement portal of the Government.
2. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.
3. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
4. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.
5. The successful bidder shall furnish a performance guarantee of 5 % of the contract value within 15 days.

COMMERCIAL TERMS AND CONDITIONS

1. Payment shall be made within 30 days of receipt of bills duly certified by the Engineer-in-charge.
2. The contractor shall comply with all labour laws and the provisions of the Contract Labour Act.
3. All disputes shall be subject to arbitration under the Arbitration and

Signature of Bidder

Page 1 of 3

Conciliation Act, 1996.

4. Liquidated damages at 0.5 % per week of delay shall be levied, subject to a maximum of 10 % of the contract value.

SCOPE OF WORK

This specification covers construction of rcc elevated service reservoir complete in all respects.

SITE CONDITIONS

i) The structure shall be designed for the exposure condition severe as defined in IS 456:2000.

4 TECHNICAL SPECIFICATION — CONCRETE AND REINFORCEMENT

- i) All plain and reinforced concrete work shall conform to IS 456:2000.
- ii) All RCC work shall be of grade M30.
- iii) Nominal cover to reinforcement shall be 30mm.
- iv) The free water-cement ratio shall not exceed 0.45.
- v) Minimum cement content shall be 320 kg/m³.
- vi) Cement shall be ordinary Portland cement 43 grade conforming to IS 269:2015.
- vii) Coarse and fine aggregates shall conform to IS 383:2016.
- viii) Reinforcement shall be Fe 500D TMT bars conforming to IS 1786:2008.
- ix) Concrete shall be design mix proportioned as per IS 10262:2019.
- x) Curing shall be continued for a minimum period of 10 days.
- xi) Concrete shall be compacted with mechanical needle vibrators.

SECTION 5: TESTING, INSPECTION AND CERTIFICATION

- i) Cube tests for compressive strength shall be carried out at 7 and 28 days.
- ii) Manufacturer's test certificates shall be furnished for each lot of cement

Signature of Bidder

and reinforcement steel.

iii) The equipment shall be inspected by the Engineer-in-charge at the manufacturer's works before dispatch.

6 DOCUMENTATION, WARRANTY AND TRAINING

i) The contractor shall submit detailed shop drawings for approval within 21 days of award of work.

ii) Three sets of operation and maintenance manuals shall be handed over on completion. The complete installation shall be guaranteed against defective design, material and workmanship for a period of 12 months from the date of handing over.

iii) The contractor shall train the Department's operating staff in operation and routine maintenance.

BILL OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | RCC M30 in superstructure | cum | 420

2 | TMT reinforcement Fe 500D | MT | 58

LIST OF APPROVED MAKES

Cement: UltraTech / ACC / Ambuja; Steel: SAIL / TATA / JSW

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Note: Quantities are approximate and may vary during execution.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 3 of 3