

URBAN DEVELOPMENT AUTHORITY

??? ??????? ??????

Office of the Executive Engineer, Division No. 2

NOTICE INVITING e-TENDER No. SE/CIV/84/2026-27

Name of work: Electrical works for sewage treatment plant including motors and panels.

Estimated cost put to tender: Rs. 326,29,000/-

Earnest Money Deposit: Rs. 8,90,000/-

Period of completion: 12 months

Last date of submission: 25.10.2026 up to 15:00 hrs

SECTION I — INSTRUCTIONS TO TENDERERS

1. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
2. The tender documents may be downloaded from the e-procurement portal of the Government.
3. Conditional bids will be summarily rejected.
4. The Department reserves the right to accept or reject any bid without assigning any reason.
5. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.
6. The bid shall remain valid for 90 days from the date of opening of the technical bid.

COMMERCIAL TERMS AND CONDITIONS

1. Liquidated damages at 0.5 % per week of delay shall be levied, subject to a maximum of 10 % of the contract value.
2. All disputes shall be subject to arbitration under the Arbitration and Conciliation Act, 1996.
3. The contractor shall indemnify the Department against all claims arising out of the

Signature of Bidder

Page 1 of 6

work.

4. Rates quoted shall be inclusive of all taxes, freight, insurance and transit risks.
5. Payment shall be made within 30 days of receipt of bills duly certified by the Engineer-in-charge.

SCOPE OF WORK

This specification covers electrical works for sewage treatment plant including motors and panels complete in all respects.

SITE CONDITIONS

- The equipment shall be designed for a maximum ambient temperature of 40 deg C.
- Relative humidity at site may reach 95%.
- The installation is at an altitude of less than 1000 m above mean sea level.

SECTION 4: MAIN LT PANEL

- The LT panel shall conform to IS/IEC 61439-1:2020 and IS/IEC 61439-2:2020.
- The panel shall be cubicle type, floor mounted, fabricated from CRCA sheet steel of 2mm thickness.
- The rated operational voltage shall be 415V, 3 phase, 4 wire, 50Hz.
- Main busbars shall be of electrolytic grade aluminium rated for 1600A continuous current. The busbars and panel shall withstand a short circuit current of 50 kA for 1 second.
- The degree of protection of the panel enclosure shall be IP54.
- The switchboard shall have Form 3b internal separation.
- Incomers shall be 1600A, 4 pole, electrically operated air circuit breakers conforming to IS/IEC 60947-2:2003.
- Outgoing feeders shall be MCCBs with ultimate breaking capacity of 36 kA.
- Multifunction meters of accuracy class 0.5 shall be provided on each incomer.

Signature of Bidder

GUARANTEED TECHNICAL PARTICULARS — LT PANEL

Rated voltage: 415V

Rated current of main busbar: 1600A

Short time current rating: 50 kA for 1 s

Degree of protection: IP54

Make and type: (to be furnished by the bidder)

5 TECHNICAL SPECIFICATION — DRIVE MOTORS

- Motors shall be squirrel cage induction motors conforming to IS 325:1996.
- The rated output of the motor shall be 37kW. Motors shall be suitable for $415V \pm 10\%$, $50Hz \pm 5\%$, 3 phase supply.
- Motors shall be of efficiency class IE3 as per IS 12615:2018.
- Degree of protection of the motor enclosure shall be IP55. Motors shall have class F insulation with temperature rise limited to class B and shall be suitable for S1 duty.
- Synchronous speed of the motor shall be 1500 RPM.

PART F — LT POWER AND CONTROL CABLES

- Power cables shall be 1.1 kV grade, aluminium conductor, XLPE insulated, armoured and PVC sheathed, conforming to IS 7098 (Part 1):1988.
- The main feeder cable shall be 3.5 core 300 sq mm.
- The cables shall be suitable for a maximum continuous conductor temperature of 90 deg C.
- Control cables shall be PVC insulated, copper conductor of 2.5 sq mm, 1.1 kV grade, conforming to IS 1554 (Part 1).
- Conductors shall be stranded, class 2, conforming to IS 8130.
- Cables shall be laid in RCC trenches or on perforated cable trays as shown in the drawings.

Signature of Bidder

Page 3 of 6

- Cable ends shall be terminated using double compression glands and crimped lugs. Each drum shall be marked with the manufacturer's name, size, voltage grade and year of manufacture.

SECTION 7: TESTING, INSPECTION AND CERTIFICATION

- Routine verification of each assembly shall be carried out in accordance with IS/IEC 61439-1.
- Type test certificates of the offered panel design from a NABL accredited laboratory shall be submitted.
- Routine tests on motors shall be carried out as per IS 4029.
- Motors shall bear the ISI mark.
- Cables shall be tested in accordance with IS 10810.
- Routine test certificates of cables shall be furnished with each consignment.
- The equipment shall be inspected by the Engineer-in-charge at the manufacturer's works before dispatch.

8 DOCUMENTATION, WARRANTY AND TRAINING

- The contractor shall submit detailed shop drawings for approval within 21 days of award of work.
- Three sets of operation and maintenance manuals shall be handed over on completion.
- The complete installation shall be guaranteed against defective design, material and workmanship for a period of 12 months from the date of handing over.
- The contractor shall train the Department's operating staff in operation and routine maintenance.

BILL OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | Main LT panel as per specification | Set | 1

Signature of Bidder

- 2 | Sub-distribution board, 12 way TPN | No. | 8
- 3 | Squirrel cage induction motor 37 kW, 1500 rpm | No. | 3
- 4 | 3.5C x 300 sq mm XLPE armoured cable | m | 350
- 5 | Cable tray 300 mm wide | m | 120

LIST OF APPROVED MAKES

LT panel builder: as per approved list; ACB/MCCB: L&T / Siemens / Schneider / ABB

Motors: ABB / Siemens / Crompton Greaves / Kirloskar

Cables: Polycab / KEI / Havells / RR Kabel

Note: Drawings are indicative only and shall be verified at site.

Note: Quantities are approximate and may vary during execution.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 5 of 6

