

PUBLIC WORKS DEPARTMENT

????????? ???????

Office of the Executive Engineer, Project Division

NOTICE INVITING e-TENDER No. CE/CIV/54/2026-27

Name of work: Hostel block construction — civil and internal electrical works.

Estimated cost put to tender: Rs. 64,62,000/-

Earnest Money Deposit: Rs. 1,42,000/-

Period of completion: 18 months

Last date of submission: 14.11.2026 up to 15:00 hrs

INSTRUCTIONS TO BIDDERS

1. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
2. The Department reserves the right to accept or reject any bid without assigning any reason.
3. The bidder must be registered with the Department in the appropriate class.
4. The tender documents may be downloaded from the e-procurement portal of the Government.

SPECIAL CONDITIONS OF CONTRACT

1. Rates quoted shall be inclusive of all taxes, freight, insurance and transit risks.
2. Payment shall be made within 30 days of receipt of bills duly certified by the Engineer-in-charge.
3. Income tax and GST shall be deducted at source as applicable.
4. All disputes shall be subject to arbitration under the Arbitration and Conciliation Act, 1996.
5. The contractor shall comply with all labour laws and the provisions of the Contract Labour Act.

SCOPE OF WORK

Signature of Bidder

Page 1 of 4

This specification covers hostel block construction — civil and internal electrical works complete in all respects.

SITE CONDITIONS

1. The structure shall be designed for the exposure condition severe as defined in IS 456:2000.

PART D — CONCRETE AND REINFORCEMENT

1. All plain and reinforced concrete work shall conform to IS 456:2000.
2. All RCC work shall be of grade M30.
3. Nominal cover to reinforcement shall be 45mm.
4. The free water-cement ratio shall not exceed 0.45.
5. Minimum cement content shall be 320 kg/m³.
6. Cement shall be ordinary Portland cement 43 grade conforming to IS 269:2015.
7. Coarse and fine aggregates shall conform to IS 383:2016.
8. Reinforcement shall be Fe 500D TMT bars conforming to IS 1786:2008.
9. Concrete shall be design mix proportioned as per IS 10262:2019. Distribution boards and enclosures shall be of suitable size.
10. Curing shall be continued for a minimum period of 10 days.
11. Concrete shall be compacted with mechanical needle vibrators.

PART E — INTERNAL WIRING AND EARTHING

1. Wiring shall be carried out as per IS 732:1989.
2. The supply system shall be TN-S earthing arrangement.
3. Wiring shall be concealed in rigid PVC conduits of 1.5mm wall thickness.
4. Wires shall be FR PVC insulated, single core, stranded copper conductor of 450/750 V grade conforming to IS 694:2010.
5. Lighting circuits shall be wired with 1.5 sq mm and power circuits with 4 sq mm copper conductors.

Signature of Bidder

6. Miniature circuit breakers shall conform to IS/IEC 60898-1 and shall have a breaking capacity of 10kA.
7. MCB ratings shall range from 6A to 32A as shown in the single line diagram.
8. RCCBs with rated residual operating current of 30 mA shall be provided for all socket outlet circuits and shall conform to IS 12640 (Part 1).
9. Earthing shall be carried out in accordance with IS 3043:2018.
10. Two numbers of pipe earth electrodes shall be provided for the main distribution board.
11. The earth resistance shall not exceed 1 ohms.

6 TESTS AND INSPECTION

1. Compressive strength tests shall be carried out as per IS 516 (Part 1/Sec 1):2021.
2. Manufacturer's test certificates shall be furnished for each lot of cement and reinforcement steel.
3. Wires shall be tested in accordance with IS 10810.
4. On completion, insulation resistance and earth continuity tests shall be carried out in accordance with IS 732.
5. Wires, MCBs and RCCBs shall be ISI marked.
6. The equipment shall be inspected by the Engineer-in-charge at the manufacturer's works before dispatch.

7 DOCUMENTATION, WARRANTY AND TRAINING

1. The contractor shall submit detailed shop drawings for approval within 21 days of award of work. Three sets of operation and maintenance manuals shall be handed over on completion.
2. The complete installation shall be guaranteed against defective design, material and workmanship for a period of 12 months from the date of handing over.
3. The contractor shall train the Department's operating staff in operation and routine maintenance.

Signature of Bidder

SCHEDULE OF QUANTITIES

Sl. No. | Description | Unit | Qty

- | | | | |
|---|---|-------|-----|
| 1 | RCC M30 in superstructure | cum | 420 |
| 2 | TMT reinforcement Fe 500D | MT | 58 |
| 3 | Point wiring for light point with 1.5 sq mm FR PVC wire | Point | 240 |
| 4 | 4 way SPN distribution board | No. | 16 |

APPROVED MAKES OF MATERIALS

Cement: UltraTech / ACC / Ambuja; Steel: SAIL / TATA / JSW

Wires: Polycab / Havells / Finolex; MCB/RCCB: Legrand / Schneider / Havells

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Note: Quantities are approximate and may vary during execution.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 4 of 4