

CENTRAL PUBLIC WORKS DEPARTMENT

??? ?????? ??????

Office of the Executive Engineer, Circle I

NOTICE INVITING e-TENDER No. CE/MM/34/2026-27

Name of work: Supply, installation, testing and commissioning of LT electrical distribution system.

Estimated cost put to tender: Rs. 99,81,000/-

Earnest Money Deposit: Rs. 8,74,000/-

Period of completion: 12 months

Last date of submission: 23.10.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
2. The tender documents may be downloaded from the e-procurement portal of the Government.
3. The bidder must be registered with the Department in the appropriate class.
4. The successful bidder shall furnish a performance guarantee of 5 % of the contract value within 15 days.

SCOPE OF WORK

This specification covers supply, installation, testing and commissioning of It electrical distribution system complete in all respects.

SITE CONDITIONS

- i) The equipment shall be designed for a maximum ambient temperature of 40°C.
- ii) Relative humidity at site may reach 95%.
- iii) The installation is at an altitude of less than 1000 m above mean sea level.

Signature of Bidder

PART D — MAIN LT PANEL

- i) The LT panel shall conform to IS/IEC 61439-1:2020 and IS/IEC 61439-2:2020.
- ii) The panel shall be cubicle type, floor mounted, fabricated from CRCA sheet steel of 2 mm thickness.
- iii) The rated operational voltage shall be 415V, 3 phase, 4 wire, 50 Hz.
- iv) Main busbars shall be of electrolytic grade aluminium rated for 1600 A continuous current.
- v) The busbars and panel shall withstand a short circuit current of 50kA for 1 second.
- vi) The degree of protection of the panel enclosure shall be IP54.
- vii) The switchboard shall have Form 3b internal separation.
- viii) Incomers shall be 1600 A, 4 pole, electrically operated air circuit breakers conforming to IS/IEC 60947-2:2003.
- ix) Outgoing feeders shall be MCCBs with ultimate breaking capacity of 36kA.
- x) Multifunction meters of accuracy class 0.5 shall be provided on each incomer.

GUARANTEED TECHNICAL PARTICULARS — LT PANEL

Rated voltage: 415V

Rated current of main busbar: 1600 A

Short time current rating: 50kA for 1 s

Degree of protection: IP54

Make and type: (to be furnished by the bidder)

PART E — LT POWER AND CONTROL CABLES

- i) Power cables shall be 1.1 kV grade, aluminium conductor, XLPE insulated, armoured and PVC sheathed, conforming to IS 7098 (Part 1):1988.
- ii) The main feeder cable shall be 3.5 core 300 sq mm.
- iii) The cables shall be suitable for a maximum continuous conductor temperature of 90°C.
- iv) Control cables shall be PVC insulated, copper conductor of 2.5 sq mm, 1.1 kV grade, conforming to IS 1554 (Part 1).

Signature of Bidder

- v) Conductors shall be stranded, class 2, conforming to IS 8130.
- vi) Cables shall be laid in RCC trenches or on perforated cable trays as shown in the drawings. Cable ends shall be terminated using double compression glands and crimped lugs.
- vii) Each drum shall be marked with the manufacturer's name, size, voltage grade and year of manufacture.

6 TESTS AND INSPECTION

- i) Routine verification of each assembly shall be carried out in accordance with IS/IEC 61439-1.
- ii) Type test certificates of the offered panel design from a NABL accredited laboratory shall be submitted.
- iii) Routine test certificates of cables shall be furnished with each consignment.
- iv) The equipment shall be inspected by the Engineer-in-charge at the manufacturer's works before dispatch.

7 DOCUMENTATION, WARRANTY AND TRAINING

- i) The contractor shall submit detailed shop drawings for approval within 21 days of award of work.
- ii) Three sets of operation and maintenance manuals shall be handed over on completion.
- iii) The complete installation shall be guaranteed against defective design, material and workmanship for a period of 12 months from the date of handing over.
- iv) The contractor shall train the Department's operating staff in operation and routine maintenance.

SCHEDULE OF QUANTITIES

Sl. No. | Description | Unit | Qty

- 1 | Main LT panel as per specification | Set | 1
- 2 | Sub-distribution board, 12 way TPN | No. | 8

Signature of Bidder

3 | 3.5C x 300 sq mm XLPE armoured cable | m | 350

4 | Cable tray 300 mm wide | m | 120

APPROVED MAKES OF MATERIALS

LT panel builder: as per approved list; ACB/MCCB: L&T / Siemens / Schneider / ABB

Cables: Polycab / KEI / Havells / RR Kabel

Note: Quantities are approximate and may vary during execution.

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 4 of 4