

PUBLIC HEALTH ENGINEERING DEPARTMENT

Office of the Executive Engineer, Electrical Division

NOTICE INVITING e-TENDER No. EE/CIV/13/2026-27

Name of work: Supply and installation of borewell submersible pumpsets and water quality testing.

Estimated cost put to tender: Rs. 179,66,000/-

Earnest Money Deposit: Rs. 5,29,000/-

Period of completion: 12 months

Last date of submission: 25.10.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. Conditional bids will be summarily rejected.
2. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.
3. The Department reserves the right to accept or reject any bid without assigning any reason.
4. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.
5. The tender documents may be downloaded from the e-procurement portal of the Government.
6. Bids received after the due date and time shall not be considered.
7. The bidder must be registered with the Department in the appropriate class.

SPECIAL CONDITIONS OF CONTRACT

1. All disputes shall be subject to arbitration under the Arbitration and Conciliation Act, 1996.
2. The contractor shall indemnify the Department against all claims arising out of the work.

Signature of Bidder

3. Rates quoted shall be inclusive of all taxes, freight, insurance and transit risks.
4. Payment shall be made within 30 days of receipt of bills duly certified by the Engineer-in-charge.

SCOPE OF WORK

This specification covers supply and installation of borewell submersible pumpsets and water quality testing complete in all respects.

3 TECHNICAL SPECIFICATION — BOREWELL SUBMERSIBLE PUMPSETS

- 3.1 Submersible pumpsets shall be manufactured to IS 8034:2018.
- 3.2 Duty point of each pumpset shall be 18 cum/hr at 90 m total head.
- 3.3 Overall pumpset efficiency at duty point shall be minimum 52 per cent.
- 3.4 The submersible motor shall be of rewindable wet type as per IS 9283:2013.
- 3.5 Flat submersible cables of 3 core 6 sq mm copper, PVC insulated, shall comply with IS 694:2010 and be tested to IS 10810.
- 3.6 The starter panel shall include dry run protection, overload relay and single phasing preventer.

PART D — TREATED WATER QUALITY

- 4.1 The quality of water supplied shall meet IS 10500:2012.
- 4.2 pH value: 6.5 to 8.5
- 4.3 TDS of supplied water shall be within 2000 mg/litre.
- 4.4 Turbidity of treated water shall be limited to 1 N.T.U..
- 4.5 Fluoride content shall be within 1.0 mg/litre.
- 4.6 Nitrate as NO₃ shall be less than 45 mg/litre.
- 4.7 Arsenic content in supplied water shall be less than 0.01 mg/litre.
- 4.8 Total hardness shall be within 200 mg/litre as CaCO₃.

Signature of Bidder

4.9 Total coliforms shall be absent in any 100 ml sample.

5 TESTS AND INSPECTION

5.1 Physico-chemical tests on water samples shall follow IS 3025.

5.2 Pre-dispatch inspection shall be offered to the Department's authorised representative with 15 days notice.

6 DOCUMENTATION, WARRANTY AND TRAINING

6.1 Monthly water quality reports shall be furnished to the Department.

6.2 Shop drawings and schematic diagrams shall be got approved from the Engineer-in-charge before manufacture.

6.3 O&M manuals, as-built drawings and catalogues shall be furnished in triplicate at the time of handing over.

6.4 The supplier shall replace free of cost any part found defective within the defect liability period of 24 months.

6.5 Training of two operators for one week shall be imparted by the supplier after commissioning.

BILL OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | Submersible pumpset 18 m³/hr at 90 m head | Set | 12

2 | Water quality testing (complete set of parameters) | Sample | 48

LIST OF APPROVED MAKES

Submersible pumps: CRI / Kirloskar / Texmo

Testing laboratory: NABL accredited

Note: Quantities are approximate and may vary during execution.

Signature of Bidder

Page 3 of 4

Note: Drawings are indicative only and shall be verified at site.

Signature of Bidder with seal
Executive Engineer

Signature of Bidder
Page 4 of 4