

VIDYUT VITRAN NIGAM LIMITED

????????? ???????

Office of the Executive Engineer, Division No. 2

NOTICE INVITING e-TENDER No. EE/WS/19/2026-27

Name of work: Procurement of distribution transformers and LT cables.

Estimated cost put to tender: Rs. 221,45,000/-

Earnest Money Deposit: Rs. 9,94,000/-

Period of completion: 18 months

Last date of submission: 22.10.2026 up to 15:00 hrs

SECTION I — INSTRUCTIONS TO TENDERERS

1. The tender documents may be downloaded from the e-procurement portal of the Government.
2. The bid shall remain valid for 90 days from the date of opening of the technical bid.
3. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.
4. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.

SPECIAL CONDITIONS OF CONTRACT

1. Income tax and GST shall be deducted at source as applicable.
2. Payment shall be made within 30 days of receipt of bills duly certified by the Engineer-in-charge.
3. Liquidated damages at 0.5 % per week of delay shall be levied, subject to a maximum of 10 % of the contract value.
4. The contractor shall comply with all labour laws and the provisions of the Contract Labour Act.

Signature of Bidder

Page 1 of 4

SCOPE OF WORK

This specification covers procurement of distribution transformers and It cables complete in all respects.

PART C — DISTRIBUTION TRANSFORMERS

- (a) Distribution transformers shall be designed and manufactured to IS 1180 (Part 1):2014.
- (b) Transformer rating shall be 630 K.V.A., 11 kV / 433 V, Dyn11.
- (c) Transformers shall be outdoor type, mineral oil filled, naturally cooled, with copper windings.
- (d) Winding temperature rise shall be limited to 40 °C over a maximum ambient of 50 °C.
- (e) Transformer tank shall be fabricated from mild steel plates and epoxy painted.

SECTION 4: LT POWER AND CONTROL CABLES

- (a) LT power cables shall be XLPE insulated 1.1 kV grade armoured cables with aluminium conductors as per IS 7098 (Part 1):1988.
- (b) Continuous conductor operating temperature of XLPE cables shall be 90 °C.
- (c) Copper control cables of 2.5 sq mm shall be PVC insulated heavy duty type as per IS 1554 (Part 1).
- (d) Cable conductors shall meet the resistance requirements of IS 8130 for class 2 conductors.
- (e) Cables shall be laid directly in ground at a depth of 750 mm. with brick protection.
- (f) Terminations shall be made with brass double compression glands and tinned copper lugs.
- (g) Cable drums shall carry marking of size, type, length and manufacturer's name.

SECTION 5: TESTING, INSPECTION AND CERTIFICATION

- (a) Each transformer shall be subjected to routine tests in accordance with IS 2026

Signature of Bidder

(Part 1):2011.

- (b) The bidder shall submit type test certificates from an NABL accredited laboratory for the offered rating.
- (c) Acceptance tests on cables shall be carried out as per IS 10810 in presence of the Engineer.
- (d) Pre-dispatch inspection shall be offered to the Department's authorised representative with 15 days notice.

6 DOCUMENTATION, WARRANTY AND TRAINING

- (a) Shop drawings and schematic diagrams shall be got approved from the Engineer-in-charge before manufacture.
- (b) O&M manuals, as-built drawings and catalogues shall be furnished in triplicate at the time of handing over.
- (c) The supplier shall replace free of cost any part found defective within the defect liability period of 24 months.
- (d) Training of two operators for one week shall be imparted by the supplier after commissioning.

SCHEDULE OF QUANTITIES

Sl. No. | Description | Unit | Qty

- 1 | 630 kVA 11/0.433 kV distribution transformer | No. | 4
- 2 | 3.5C x 300 sq mm XLPE armoured cable | m | 350
- 3 | Cable tray 300 mm wide | m | 120

LIST OF APPROVED MAKES

Transformers: as per approved vendor list of the utility
Cables: Polycab / KEI / Havells / RR Kabel

Signature of Bidder

Page 3 of 4

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Note: Quantities are approximate and may vary during execution.

Signature of Bidder with seal
Executive Engineer

Signature of Bidder
Page 4 of 4