

PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer, Division No. 2

NOTICE INVITING e-TENDER No. CE/CIV/22/2026-27

Name of work: Internal electrification including wiring, distribution boards and earthing.

Estimated cost put to tender: Rs. 261,21,000/-

Earnest Money Deposit: Rs. 4,55,000/-

Period of completion: 18 months

Last date of submission: 14.10.2026 up to 15:00 hrs

INSTRUCTIONS TO BIDDERS

1. The tender documents may be downloaded from the e-procurement portal of the Government.
2. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
3. Conditional bids will be summarily rejected.
4. The bid shall remain valid for 90 days from the date of opening of the technical bid.

GENERAL CONDITIONS OF CONTRACT

1. The contractor shall comply with all labour laws and the provisions of the Contract Labour Act.
2. Liquidated damages at 0.5 % per week of delay shall be levied, subject to a maximum of 10 % of the contract value.
3. All disputes shall be subject to arbitration under the Arbitration and Conciliation Act, 1996.

SCOPE OF WORK

This specification covers internal electrification including wiring, distribution boards and earthing complete in all respects.

Signature of Bidder

PART C — INTERNAL WIRING AND EARTHING

- (a) The internal wiring installation shall comply with IS 732:2019.
- (b) Earthing arrangement of the installation shall be TN-S system.
- (c) All wiring shall be drawn through heavy gauge PVC conduits recessed in walls. All enclosures shall be of adequate size to accommodate the equipment.
- (d) Building wires shall be 1100 V grade PVC insulated multistrand copper conductor as per IS 694:2010.
- (e) Minimum conductor size shall be 1.5 Sq.mm for lighting points and 4 Sq.mm for power points.
- (f) MCBs shall be C-curve, as per IS/IEC 60898-1, with rated short circuit capacity of 10 kA.
- (g) Final circuit MCBs shall be rated between 6 Amps and 32 Amps.
- (h) Socket outlet circuits shall be protected by 30 mA RCCBs conforming to IS 12640 (Part 1).
The earthing system shall be designed and installed as per IS 3043:2018.
- (i) Main distribution board shall be earthed through two separate pipe earth electrodes.
- (j) Combined resistance of the earthing system shall be less than 1 Ohm.

4 TESTS AND INSPECTION

- (a) Samples of wires shall be tested as per IS 10810 at the manufacturer's works.
- (b) The complete wiring shall be tested before handing over.
- (c) Pre-dispatch inspection shall be offered to the Department's authorised representative with 15 days notice.

5 DOCUMENTATION, WARRANTY AND TRAINING

- (a) Shop drawings and schematic diagrams shall be got approved from the Engineer-in-charge before manufacture.
- (b) O&M manuals, as-built drawings and catalogues shall be furnished in triplicate at the time of handing over.
- (c) The supplier shall replace free of cost any part found defective within the defect liability period of 24 months.

Signature of Bidder

(d) Training of two operators for one week shall be imparted by the supplier after commissioning.

SCHEDULE OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | Point wiring for light point with 1.5 sq mm FR PVC wire | Point | 240

2 | 4 way SPN distribution board | No. | 16

LIST OF APPROVED MAKES

Wires: Polycab / Havells / Finolex; MCB/RCCB: Legrand / Schneider / Havells

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Note: Drawings are indicative only and shall be verified at site.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 3 of 3