

JAL NIGAM

?????? ?????? ?????

Office of the Executive Engineer, Electrical Division

NOTICE INVITING e-TENDER No. SE/CIV/23/2026-27

Name of work: Design, supply and commissioning of raw water pumping machinery.

Estimated cost put to tender: Rs. 303,92,000/-

Earnest Money Deposit: Rs. 1,55,000/-

Period of completion: 12 months

Last date of submission: 12.11.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. The successful bidder shall furnish a performance guarantee of 5 % of the contract value within 15 days.
2. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.
3. The bid shall remain valid for 90 days from the date of opening of the technical bid.
4. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.

SPECIAL CONDITIONS OF CONTRACT

1. The contractor shall indemnify the Department against all claims arising out of the work.
2. Payment shall be made within 30 days of receipt of bills duly certified by the Engineer-in-charge.
3. Liquidated damages at 0.5 % per week of delay shall be levied, subject to a maximum of 10 % of the contract value.
4. The contractor shall comply with all labour laws and the provisions of the Contract Labour Act.

Signature of Bidder

Page 1 of 4

5. Income tax and GST shall be deducted at source as applicable.

SCOPE OF WORK

This specification covers design, supply and commissioning of raw water pumping machinery complete in all respects.

3 TECHNICAL SPECIFICATION — HORIZONTAL CENTRIFUGAL PUMPS

1. Horizontal centrifugal pumps for clear cold water shall comply with IS 1520:1980.
2. Duty point of each pump shall be 250 m³/hr discharge at 45 mtrs total dynamic head.
3. Pump casing shall be CI and impeller of leaded tin bronze.
4. Sound pressure level shall be limited to 85 dB(A) at 1 mtrs distance.

PUMP DATA SHEET

Rated discharge: 250 m³/hr

Total dynamic head: 45 mtrs

Make and type: (to be furnished by the bidder)

4 TECHNICAL SPECIFICATION — DRIVE MOTORS

1. The drive motor shall be a three phase TEFC squirrel cage induction motor as per IS 325:1996.
2. Motor rating shall be 37 KW continuous.
3. Motors shall operate satisfactorily on a supply of 415 V $\pm$ 10 per cent and 50 Hz $\pm$ 5 per cent. The motor shall be premium efficiency IE3 conforming to IS 12615:2018.
4. Motor enclosure shall be totally enclosed fan cooled with IP 55 protection.
5. Insulation shall be class F and the motor shall be rated for S1 continuous duty.
6. Motor speed shall be 1500 r.p.m. (4 pole).

SECTION 5: LT POWER AND CONTROL CABLES

Signature of Bidder

Page 2 of 4

1. LT power cables shall be XLPE insulated 1.1 kV grade armoured cables with aluminium conductors as per IS 7098 (Part 1):1988.
2. Size of the incoming feeder cable shall be 3.5 core x 300 sq mm.
3. Continuous conductor operating temperature of XLPE cables shall be 90 Deg.C.
4. Copper control cables of 2.5 sq mm shall be PVC insulated heavy duty type as per IS 1554 (Part 1).
5. Cable conductors shall meet the resistance requirements of IS 8130 for class 2 conductors. Cables shall be laid directly in ground at a depth of 750 mm. with brick protection.
6. Terminations shall be made with brass double compression glands and tinned copper lugs. Cable drums shall carry marking of size, type, length and manufacturer's name.

6 TESTS AND INSPECTION

1. Performance tests on each pump shall be conducted as per IS 9137 in the presence of the Engineer.
2. Pumps shall carry the BIS Standard Mark.
3. Each motor shall be subjected to routine tests in accordance with IS 4029.
4. Acceptance tests on cables shall be carried out as per IS 10810 in presence of the Engineer.
5. Manufacturer's test certificates shall accompany every cable drum supplied. Pre-dispatch inspection shall be offered to the Department's authorised representative with 15 days notice.

7 DOCUMENTATION, WARRANTY AND TRAINING

1. Shop drawings and schematic diagrams shall be got approved from the Engineer-in-charge before manufacture. O&M manuals, as-built drawings and catalogues shall be furnished in triplicate at the time of handing over.
2. The supplier shall replace free of cost any part found defective within the defect

Signature of Bidder

liability period of 24 months.

3. Training of two operators for one week shall be imparted by the supplier after commissioning.

SCHEDULE OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | Horizontal centrifugal pumpset 250 m³/hr at 45 m | Set | 3

2 | Squirrel cage induction motor 37 kW, 1500 rpm | No. | 3

3 | 3.5C x 300 sq mm XLPE armoured cable | m | 350

4 | Cable tray 300 mm wide | m | 120

LIST OF APPROVED MAKES

Pumps: Kirloskar Brothers / KSB / Mather & Platt

Motors: ABB / Siemens / Crompton Greaves / Kirloskar

Cables: Polycab / KEI / Havells / RR Kabel

Note: Drawings are indicative only and shall be verified at site.

Note: Quantities are approximate and may vary during execution.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 4 of 4