

WATER SUPPLY AND DRAINAGE BOARD

Office of the Executive Engineer, Project Division

NOTICE INVITING e-TENDER No. SE/CIV/94/2026-27

Name of work: Construction of RCC elevated service reservoir.

Estimated cost put to tender: Rs. 210,34,000/-

Earnest Money Deposit: Rs. 6,26,000/-

Period of completion: 12 months

Last date of submission: 28.10.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. The bid shall remain valid for 90 days from the date of opening of the technical bid.
2. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.
3. Conditional bids will be summarily rejected.
4. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
5. Bids received after the due date and time shall not be considered.

SCOPE OF WORK

This specification covers construction of rcc elevated service reservoir complete in all respects.

SITE CONDITIONS

- (a) Exposure condition shall be considered as severe for all members.

PART D — CONCRETE AND REINFORCEMENT

- (a) Design and construction of RCC shall be in accordance with IS 456:2000.
- (b) Grade of concrete for all structural members shall be M 20.

Signature of Bidder

- (c) Clear cover to main reinforcement shall be 30mm for all members.
- (d) Maximum free water cement ratio shall be 0.45.
- (e) Cement content shall not be less than 320 kg/m³ of concrete.
- (f) OPC 43 grade cement as per IS 269:2015 shall be used.
- (g) Aggregates shall comply with the requirements of IS 383:2016.
- (h) High strength deformed bars of grade Fe 500D as per IS 1786:1985 shall be used.
- (i) Mix design shall be carried out in accordance with IS 10262:2019.
- (j) Concrete shall be kept continuously moist for at least 10 days.
- (k) Compaction shall be done by immersion vibrators.

SECTION 5: TESTING, INSPECTION AND CERTIFICATION

- (a) Cube tests for compressive strength shall be done in accordance with IS 516:1959.
- (b) Mill test certificates for steel and test certificates for cement shall be submitted for every consignment.
- (c) Pre-dispatch inspection shall be offered to the Department's authorised representative with 15 days notice.

6 DOCUMENTATION, WARRANTY AND TRAINING

- (a) Shop drawings and schematic diagrams shall be got approved from the Engineer-in-charge before manufacture.
- (b) O&M manuals, as-built drawings and catalogues shall be furnished in triplicate at the time of handing over.
- (c) The supplier shall replace free of cost any part found defective within the defect liability period of 24 months.
- (d) Training of two operators for one week shall be imparted by the supplier after commissioning.

BILL OF QUANTITIES

Signature of Bidder

Sl. No. | Description | Unit | Qty

1 | RCC M30 in superstructure | cum | 420

2 | TMT reinforcement Fe 500D | MT | 58

APPROVED MAKES OF MATERIALS

Cement: UltraTech / ACC / Ambuja; Steel: SAIL / TATA / JSW

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Note: Drawings are indicative only and shall be verified at site.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 3 of 3