

MUNICIPAL CORPORATION

?? ???? ???? ???? ???? ?

Office of the Executive Engineer, Circle I

NOTICE INVITING e-TENDER No. EE/MM/83/2026-27

Name of work: Construction of pump house with structural steel roof and electrical works.

Estimated cost put to tender: Rs. 409,30,000/-

Earnest Money Deposit: Rs. 8,47,000/-

Period of completion: 12 months

Last date of submission: 25.10.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
2. The bidder must be registered with the Department in the appropriate class.
3. Bids received after the due date and time shall not be considered.
4. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.
5. The successful bidder shall furnish a performance guarantee of 5 % of the contract value within 15 days.

COMMERCIAL TERMS AND CONDITIONS

1. The contractor shall comply with all labour laws and the provisions of the Contract Labour Act.
2. Income tax and GST shall be deducted at source as applicable.
3. Rates quoted shall be inclusive of all taxes, freight, insurance and transit risks.
4. Payment shall be made within 30 days of receipt of bills duly certified by the Engineer-in-charge.

SCOPE OF WORK

Signature of Bidder

This specification covers construction of pump house with structural steel roof and electrical works complete in all respects.

SITE CONDITIONS

(a) Exposure condition shall be considered as severe for all members.

PART D — CONCRETE AND REINFORCEMENT

(a) Design and construction of RCC shall be in accordance with IS 456:2000.

(b) Grade of concrete for all structural members shall be M 30.

(c) Clear cover to main reinforcement shall be 45 MM for all members.

(d) Maximum free water cement ratio shall be 0.45.

(e) Cement content shall not be less than 320 Kg/cum of concrete.

(f) OPC 43 GRADE CEMENT AS PER IS 8112 SHALL BE USED.

(g) AGGREGATES SHALL COMPLY WITH THE REQUIREMENTS OF IS 383:2016.

(h) High strength deformed bars of grade Fe 500D as per IS 1786:2008 shall be used. Mix design shall be carried out in accordance with IS 10262:2019.

(i) Concrete shall be kept continuously moist for at least 10 days.

(j) Compaction shall be done by immersion vibrators.

PART E — STRUCTURAL STEEL WORK

(a) Rolled steel sections shall be E250 grade as per IS 2062:2011.

(b) Steel surfaces shall be painted with red oxide primer and two finishing coats.

(c) Welding shall be done by qualified welders using approved electrodes.

6 TECHNICAL SPECIFICATION — INTERNAL WIRING AND EARTHING

(a) The internal wiring installation shall comply with IS 732:2019. EARTHING ARRANGEMENT OF THE INSTALLATION SHALL BE TN-S SYSTEM.

(b) All wiring shall be drawn through heavy gauge PVC conduits recessed in walls.

Signature of Bidder

- (c) Building wires shall be 450/750 V grade PVC insulated multistrand copper conductor as per IS 694:2010.
- (d) Minimum conductor size shall be 1.5 sq mm for lighting points and 4 sq mm for power points.
- (e) MCBs shall be C-curve, as per IS/IEC 60898-1, with rated short circuit capacity of 10kA.
- (f) Final circuit MCBs shall be rated between 6 Amp and 32 Amp.
- (g) Socket outlet circuits shall be protected by 30 mA RCCBs conforming to IS 12640 (Part 1).
- (h) The earthing system shall be designed and installed as per IS 3043:2018.
- (i) Main distribution board shall be earthed through two separate pipe earth electrodes. Combined resistance of the earthing system shall be less than 1 Ohm.

SECTION 7: TESTING, INSPECTION AND CERTIFICATION

- (a) Cube tests for compressive strength shall be done in accordance with IS 516 (Part 1/Sec 1):2021.
- (b) Mill test certificates for steel and test certificates for cement shall be submitted for every consignment.
- (c) Structural steel shall be accompanied by mill test certificates from the producer.
- (d) Tests shall be carried out on completion of the installation as per IS 732 and results recorded. ALL WIRES, MCBS AND RCCBS SHALL BEAR THE BIS STANDARD MARK.
- (e) Pre-dispatch inspection shall be offered to the Department's authorised representative with 15 days notice.

8 DOCUMENTATION, WARRANTY AND TRAINING

- (a) Shop drawings and schematic diagrams shall be got approved from the Engineer-in-charge before manufacture. O&M manuals, as-built drawings and catalogues shall be furnished in triplicate at the time of handing over.
- (b) The supplier shall replace free of cost any part found defective within the defect liability period of 24 months.
- (c) Training of two operators for one week shall be imparted by the supplier after

Signature of Bidder

commissioning.

SCHEDULE OF QUANTITIES

Sl. No. | Description | Unit | Qty

- 1 | RCC M30 in superstructure | cum | 420
- 2 | TMT reinforcement Fe 500D | MT | 58
- 3 | Structural steel work in trusses and purlins | MT | 22
- 4 | Point wiring for light point with 1.5 sq mm FR PVC wire | Point | 240
- 5 | 4 way SPN distribution board | No. | 16

LIST OF APPROVED MAKES

Cement: UltraTech / ACC / Ambuja; Steel: SAIL / TATA / JSW

Steel: SAIL / TATA / JSW

Wires: Polycab / Havells / Finolex; MCB/RCCB: Legrand / Schneider / Havells

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Note: Drawings are indicative only and shall be verified at site.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 4 of 4