

CENTRAL PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer, Division No. 2

NOTICE INVITING e-TENDER No. CE/ELE/23/2026-27

Name of work: Supply, installation, testing and commissioning of LT electrical distribution system.

Estimated cost put to tender: Rs. 413,55,000/-

Earnest Money Deposit: Rs. 3,79,000/-

Period of completion: 6 months

Last date of submission: 19.11.2026 up to 15:00 hrs

INSTRUCTIONS TO BIDDERS

1. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.
2. The Department reserves the right to accept or reject any bid without assigning any reason.
3. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.
4. The tender documents may be downloaded from the e-procurement portal of the Government.

GENERAL CONDITIONS OF CONTRACT

1. Liquidated damages at 0.5 % per week of delay shall be levied, subject to a maximum of 10 % of the contract value.
2. Income tax and GST shall be deducted at source as applicable.
3. Rates quoted shall be inclusive of all taxes, freight, insurance and transit risks.
4. The contractor shall indemnify the Department against all claims arising out of the work.
5. The contractor shall comply with all labour laws and the provisions of the Contract

Signature of Bidder

Labour Act.

SCOPE OF WORK

This specification covers supply, installation, testing and commissioning of It electrical distribution system complete in all respects.

SITE CONDITIONS

- i) All equipment shall be suitable for operation at an ambient air temperature not exceeding 40 Deg.C. The equipment shall be suitable for relative humidity up to 95 per cent.
- ii) Site altitude does not exceed 1000 m above MSL.

SECTION 4: MAIN LT PANEL

- i) Switchboards shall be designed, manufactured and tested in accordance with IS/IEC 61439-1:2020 and IS/IEC 61439-2:2020.
- ii) Panels shall be free standing, totally enclosed, made of 2 mm. thick CRCA sheet with powder coated finish.
- iii) The panel shall be suitable for 415 Volts $\pm$ 10 per cent, 50 Hz, 3 phase 4 wire system.
- iv) The horizontal busbar shall be high conductivity aluminium alloy of 1600A rating.
- v) Short time withstand rating of the switchboard shall be 50kA for 1 s.
- vi) Enclosure protection class for the switchboard shall be IP 54.
- vii) Internal separation of functional units shall be Form 4.
- viii) Incoming breaker shall be 1600A four pole draw-out ACB as per IS/IEC 60947-2:2003 with microprocessor release.
- ix) All outgoing MCCBs shall have a rated service breaking capacity of not less than 36kA.
- x) Each incomer shall be provided with a digital multifunction meter with RS-485 port.

Signature of Bidder

GUARANTEED TECHNICAL PARTICULARS — LT PANEL

Rated operational voltage: 415 Volts

Busbar current rating: 1600A

Rated short-time withstand current: 50kA for 1 sec

Enclosure protection: IP54

Make and type: (to be furnished by the bidder)

5 TECHNICAL SPECIFICATION — LT POWER AND CONTROL CABLES

i) LT power cables shall be XLPE insulated 1.1 kV grade armoured cables with aluminium conductors as per IS 7098 (Part 1):1988.

ii) Size of the incoming feeder cable shall be 3.5 core x 300 sqmm.

iii) Continuous conductor operating temperature of XLPE cables shall be 90 Deg.C. Copper control cables of 2.5 sqmm shall be PVC insulated heavy duty type as per IS 1554 (Part 1).

iv) Cable conductors shall meet the resistance requirements of IS 8130 for class 2 conductors.

v) Cables shall be laid directly in ground at a depth of 750 mm. with brick protection.

vi) Terminations shall be made with brass double compression glands and tinned copper lugs. Cable drums shall carry marking of size, type, length and manufacturer's name.

6 TESTS AND INSPECTION

i) Each switchboard shall be subjected to routine verification tests as per IS/IEC 61439-1 at the works.

ii) The bidder shall furnish type test reports of the switchboard and breakers from an NABL accredited laboratory.

iii) Acceptance tests on cables shall be carried out as per IS 10810 in presence of the Engineer.

Signature of Bidder

Page 3 of 5

iv) Manufacturer's test certificates shall accompany every cable drum supplied. Pre-dispatch inspection shall be offered to the Department's authorised representative with 15 days notice.

7 DOCUMENTATION, WARRANTY AND TRAINING

- i) Shop drawings and schematic diagrams shall be got approved from the Engineer-in-charge before manufacture.
- ii) O&M manuals, as-built drawings and catalogues shall be furnished in triplicate at the time of handing over.
- iii) The supplier shall replace free of cost any part found defective within the defect liability period of 24 months.
- iv) Training of two operators for one week shall be imparted by the supplier after commissioning.

BILL OF QUANTITIES

Sl. No. | Description | Unit | Qty

- 1 | Main LT panel as per specification | Set | 1
- 2 | Sub-distribution board, 12 way TPN | No. | 8
- 3 | 3.5C x 300 sq mm XLPE armoured cable | m | 350
- 4 | Cable tray 300 mm wide | m | 120

LIST OF APPROVED MAKES

LT panel builder: as per approved list; ACB/MCCB: L&T / Siemens / Schneider / ABB

Cables: Polycab / KEI / Havells / RR Kabel

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Note: Quantities are approximate and may vary during execution.

Signature of Bidder

Signature of Bidder with seal
Executive Engineer

Signature of Bidder
Page 5 of 5