

PUBLIC WORKS DEPARTMENT

??? ?????? ??????

Office of the Executive Engineer, Division No. 2

NOTICE INVITING e-TENDER No. SE/MM/44/2026-27

Name of work: Internal electrification including wiring, distribution boards and earthing.

Estimated cost put to tender: Rs. 371,40,000/-

Earnest Money Deposit: Rs. 1,44,000/-

Period of completion: 18 months

Last date of submission: 27.12.2026 up to 15:00 hrs

INSTRUCTIONS TO BIDDERS

1. The bidder must be registered with the Department in the appropriate class.
2. The tender documents may be downloaded from the e-procurement portal of the Government.
3. Conditional bids will be summarily rejected.
4. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
5. Bids received after the due date and time shall not be considered.
6. The Department reserves the right to accept or reject any bid without assigning any reason.
7. The successful bidder shall furnish a performance guarantee of 5 % of the contract value within 15 days.

COMMERCIAL TERMS AND CONDITIONS

1. Income tax and GST shall be deducted at source as applicable.
2. Rates quoted shall be inclusive of all taxes, freight, insurance and transit risks.

Signature of Bidder

3. The contractor shall indemnify the Department against all claims arising out of the work.

SCOPE OF WORK

This specification covers internal electrification including wiring, distribution boards and earthing complete in all respects.

3 TECHNICAL SPECIFICATION — INTERNAL WIRING AND EARTHING

- (a) All wiring work shall comply with IS 732:2019.
- (b) The earthing arrangement of the supply system is TN-S.
- (c) All wiring shall run concealed in rigid PVC conduit having 1.5 m.m. wall thickness.
- (d) Wires are to be single core, stranded copper conductor, FR PVC insulated, 450/750 V grade to IS 694:2010.
- (e) Copper conductors of 1.5 mm² shall be used for lighting circuits and 4 mm² for power circuits.
- (f) MCBs shall comply with IS/IEC 60898-1 and have a rated short-circuit capacity of 10 kA rms.
- (g) MCBs from 6 ampere up to 32 ampere shall be provided as per the single line diagram.
- (h) All socket outlet circuits shall be protected by 30 mA RCCBs complying with IS 12640 (Part 1).
- (i) The earthing installation shall comply with IS 3043:1987.
- (j) The main distribution board shall be earthed through two pipe earth electrodes.
- (k) Resistance of the earthing system shall be not more than 1 Ohms.

4 TESTS AND INSPECTION

Signature of Bidder

Page 2 of 4

- (a) Testing of wires shall be done as per IS 10810.
- (b) After completion, the insulation resistance and earth continuity of the installation shall be tested as per IS 732.
- (c) All wires, MCBs and RCCBs supplied shall carry the ISI mark.
- (d) Before despatch, the Engineer-in-charge will inspect the equipment at the maker's works.

5 DOCUMENTATION, WARRANTY AND TRAINING

- (a) Detailed shop drawings are to be submitted by the contractor for approval not later than 21 calendar days after the award of work.
- (b) On completion the contractor shall hand over three copies of the O&M manuals.
- (c) The contractor shall guarantee the whole installation for 12 months after handing over against faulty design, materials and workmanship.
- (d) Operation and routine maintenance training shall be given by the contractor to the Department's operators.

BILL OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | Point wiring for light point with 1.5 sq mm FR PVC wire | Point | 240

2 | 4 way SPN distribution board | No. | 16

APPROVED MAKES OF MATERIALS

Wires: Polycab / Havells / Finolex; MCB/RCCB: Legrand / Schneider / Havells

Note: Drawings are indicative only and shall be verified at site.

Note: Quantities are approximate and may vary during execution.

Signature of Bidder

Signature of Bidder with seal
Executive Engineer

Signature of Bidder
Page 4 of 4