

JAL NIGAM

?????? ????????????

Office of the Executive Engineer, Division No. 2

NOTICE INVITING e-TENDER No. EE/CIV/43/2026-27

Name of work: Design, supply and commissioning of raw water pumping machinery.

Estimated cost put to tender: Rs. 258,12,000/-

Earnest Money Deposit: Rs. 5,82,000/-

Period of completion: 6 months

Last date of submission: 23.11.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
2. The bidder must be registered with the Department in the appropriate class.
3. The successful bidder shall furnish a performance guarantee of 5 % of the contract value within 15 days.
4. The bid shall remain valid for 90 days from the date of opening of the technical bid.
5. Bids received after the due date and time shall not be considered.

GENERAL CONDITIONS OF CONTRACT

1. Payment shall be made within 30 days of receipt of bills duly certified by the Engineer-in-charge.
2. All disputes shall be subject to arbitration under the Arbitration and Conciliation Act, 1996.
3. Liquidated damages at 0.5 % per week of delay shall be levied, subject to a maximum of 10 % of the contract value.

SCOPE OF WORK

Signature of Bidder

Page 1 of 5

This specification covers design, supply and commissioning of raw water pumping machinery complete in all respects.

3 TECHNICAL SPECIFICATION — HORIZONTAL CENTRIFUGAL PUMPS

- (a) The pumps shall comply with IS 1520:1980.
- (b) Duty point of each pump shall be 250 m³/h at 45 metre total head.
- (c) Pump efficiency at the duty point shall be 78% (percent) minimum.
- (d) The pump casing shall be cast iron and the impeller bronze.
- (e) The pumpset noise level measured 1 metre away shall be limited to 85 decibels (A).

PUMP DATA SHEET

Rated discharge: 250 m³/h

Rated total head: 45 metre

Make and type: (to be furnished by the bidder)

4 TECHNICAL SPECIFICATION — DRIVE MOTORS

- (a) Squirrel cage induction motors complying with IS 325:1996 shall be supplied.
- (b) Motor rated output shall be 37 kilowatt.
- (c) Motors are to operate on 415 V AC $\pm$ 10% (percent), 50 Hertz $\pm$ 5% (percent), three phase supply.
- (d) Motors shall meet efficiency class IE3 of IS 12615:2018.
- (e) The motor enclosure shall have IP55 degree of protection.
- (f) Insulation shall be class F, with temperature rise restricted to class B, for continuous S1 duty.
- (g) The motor synchronous speed shall be 1500 rev/min.

PART E — LT POWER AND CONTROL CABLES

- (a) LT power cables shall be aluminium conductor, XLPE insulated, armoured, PVC

Signature of Bidder

sheathed, 1.1 kV grade, complying with IS 7098 (Part 1):1988.

- (b) The size of the main feeder cable shall be 3.5 core 300 Sq mm.
- (c) Maximum continuous conductor temperature of the cables shall be 90 °C.
- (d) Copper conductor control cables of 2.5 Sq mm, PVC insulated, 1.1 kV grade shall comply with IS 1554 (Part 1).
- (e) Class 2 stranded conductors complying with IS 8130 shall be used.
- (f) Cables shall be run in RCC trenches or on perforated trays as per drawings.
- (g) Double compression glands and crimped lugs shall be used for all cable terminations.
- (h) The maker's name, size, voltage grade and year of manufacture shall be marked on every drum.

SECTION 6: TESTING, INSPECTION AND CERTIFICATION

- (a) Works testing of the pumps shall be done as per IS 9137.
- (b) Each motor shall be subjected to routine tests as per IS 4029.
- (c) All motors shall carry the ISI mark.
- (d) Testing of the cables shall be done as per IS 10810.
- (e) Each consignment of cables shall be accompanied by routine test certificates.
- (f) Before despatch, the Engineer-in-charge will inspect the equipment at the maker's works.

7 DOCUMENTATION, WARRANTY AND TRAINING

- (a) Detailed shop drawings are to be submitted by the contractor for approval not later than 21 calendar days after the award of work.
- (b) On completion the contractor shall hand over three copies of the O&M manuals.
- (c) The contractor shall guarantee the whole installation for 12 months after handing over against faulty design, materials and workmanship.
- (d) Operation and routine maintenance training shall be given by the contractor to the Department's operators.

Signature of Bidder

SCHEDULE OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | Horizontal centrifugal pumpset 250 m³/hr at 45 m | Set | 3

2 | Squirrel cage induction motor 37 kW, 1500 rpm | No. | 3

3 | 3.5C x 300 sq mm XLPE armoured cable | m | 350

4 | Cable tray 300 mm wide | m | 120

APPROVED MAKES OF MATERIALS

Pumps: Kirloskar Brothers / KSB / Mather & Platt

Motors: ABB / Siemens / Crompton Greaves / Kirloskar

Cables: Polycab / KEI / Havells / RR Kabel

Note: Quantities are approximate and may vary during execution.

Note: Drawings are indicative only and shall be verified at site.

Signature of Bidder with seal

Executive Engineer

Signature of Bidder

Page 4 of 5

