

VIDYUT VITRAN NIGAM LIMITED

?????? ????????????

Office of the Executive Engineer, Project Division

NOTICE INVITING e-TENDER No. SE/CIV/14/2026-27

Name of work: Procurement of distribution transformers and LT cables.

Estimated cost put to tender: Rs. 386,56,000/-

Earnest Money Deposit: Rs. 2,93,000/-

Period of completion: 9 months

Last date of submission: 10.12.2026 up to 15:00 hrs

#### PART A — INSTRUCTIONS TO BIDDERS

1. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.
2. The tender documents may be downloaded from the e-procurement portal of the Government.
3. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.
4. The bid shall remain valid for 90 days from the date of opening of the technical bid.
5. The successful bidder shall furnish a performance guarantee of 5 % of the contract value within 15 days.
6. Bids received after the due date and time shall not be considered.
7. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.

#### COMMERCIAL TERMS AND CONDITIONS

1. The contractor shall indemnify the Department against all claims arising out of the work.
2. Payment shall be made within 30 days of receipt of bills duly certified by the

Signature of Bidder

Page 1 of 4

Engineer-in-charge.

3. All disputes shall be subject to arbitration under the Arbitration and Conciliation Act, 1996.

#### SCOPE OF WORK

This specification covers procurement of distribution transformers and It cables complete in all respects.

#### PART C — DISTRIBUTION TRANSFORMERS

- Distribution transformers shall comply with IS 1180 (Part 1):2014. Transformer rating shall be 630 kva, 11/0.433 kV, vector group Dyn11.
- Transformers shall comply with energy efficiency level 2 of IS 1180 (Part 1).
- Transformers shall be outdoor type, copper wound, oil immersed with ONAN cooling.
- The top oil temperature rise shall be limited to 35 ° above an ambient of 50 °.
- The tank shall be fabricated from welded mild steel with epoxy paint finish.

#### SECTION 4: LT POWER AND CONTROL CABLES

- LT power cables shall be aluminium conductor, XLPE insulated, armoured, PVC sheathed, 1.1 kV grade, complying with IS 7098 (Part 1):1988. The size of the main feeder cable shall be 3.5 core 300 mm<sup>2</sup>.
- Maximum continuous conductor temperature of the cables shall be 90 °.
- Copper conductor control cables of 2.5 mm<sup>2</sup>, PVC insulated, 1.1 kV grade shall comply with IS 1554 (Part 1).
- Class 2 stranded conductors complying with IS 8130 shall be used.
- Cables shall be run in RCC trenches or on perforated trays as per drawings.
- Double compression glands and crimped lugs shall be used for all cable terminations.
- The maker's name, size, voltage grade and year of manufacture shall be marked on every drum.

Signature of Bidder

#### 5 TESTS AND INSPECTION

- Each transformer shall be subjected to all routine tests as per IS 2026 (Part 1):2011.
- Testing of the cables shall be done as per IS 10810.
- Each consignment of cables shall be accompanied by routine test certificates. Before despatch, the Engineer-in-charge will inspect the equipment at the maker's works.

#### 6 DOCUMENTATION, WARRANTY AND TRAINING

- Detailed shop drawings are to be submitted by the contractor for approval not later than 21 calendar days after the award of work.
- On completion the contractor shall hand over three copies of the O&M manuals. The contractor shall guarantee the whole installation for 12 months after handing over against faulty design, materials and workmanship.
- Operation and routine maintenance training shall be given by the contractor to the Department's operators.

#### SCHEDULE OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | 630 kVA 11/0.433 kV distribution transformer | No. | 4

2 | 3.5C x 300 sq mm XLPE armoured cable | m | 350

3 | Cable tray 300 mm wide | m | 120

#### APPROVED MAKES OF MATERIALS

Transformers: as per approved vendor list of the utility

Cables: Polycab / KEI / Havells / RR Kabel

Note: Quantities are approximate and may vary during execution.

Note: In case of any discrepancy between drawings and specifications, the decision of

Signature of Bidder

Page 3 of 4

the Engineer-in-charge shall be final.

Signature of Bidder with seal  
Executive Engineer

Signature of Bidder  
Page 4 of 4