

WATER SUPPLY AND DRAINAGE BOARD

?? ???? ???? ???? ???? ?

Office of the Executive Engineer, Electrical Division

NOTICE INVITING e-TENDER No. EE/WS/82/2026-27

Name of work: Construction of RCC elevated service reservoir.

Estimated cost put to tender: Rs. 250,62,000/-

Earnest Money Deposit: Rs. 6,61,000/-

Period of completion: 18 months

Last date of submission: 18.11.2026 up to 15:00 hrs

PART A — INSTRUCTIONS TO BIDDERS

1. Conditional bids will be summarily rejected.
2. The bidder shall upload scanned copies of GST registration, PAN and audited balance sheets.
3. Bidders shall have completed at least one similar work of value not less than 40 % of the estimated cost during the last seven years.
4. The bidder shall submit the EMD in the form of online payment or bank guarantee from a scheduled bank.
5. The bidder must be registered with the Department in the appropriate class.
6. The bid shall remain valid for 90 days from the date of opening of the technical bid.
7. The successful bidder shall furnish a performance guarantee of 5 % of the contract value within 15 days.

COMMERCIAL TERMS AND CONDITIONS

1. All disputes shall be subject to arbitration under the Arbitration and Conciliation Act, 1996.
2. The contractor shall indemnify the Department against all claims arising out

Signature of Bidder

of the work.

3. The contractor shall comply with all labour laws and the provisions of the Contract Labour Act.
4. Payment shall be made within 30 days of receipt of bills duly certified by the Engineer-in-charge.
5. Income tax and GST shall be deducted at source as applicable.

SCOPE OF WORK

This specification covers construction of rcc elevated service reservoir complete in all respects.

SITE CONDITIONS

- i) Exposure condition for the design of the structure shall be taken as severe in terms of IS 456:2000.

SECTION 4: CONCRETE AND REINFORCEMENT

- i) Plain and reinforced cement concrete works shall comply with IS 456:2000.
 - ii) Grade of concrete for all RCC members shall be M30. The nominal cover to reinforcement shall be 45 millimetre.
 - iii) Maximum free water-cement ratio shall be 0.55.
 - iv) Cement content shall be not less than 320 kg/cu.m.
 - v) OPC 43 grade cement complying with IS 269:2015 shall be used.
 - vi) Aggregates, both coarse and fine, shall comply with IS 383:2016.
 - vii) Fe 500D TMT reinforcement bars complying with IS 1786:1985 shall be used.
- Mix proportioning of concrete shall be done as per IS 10262:2019.
- viii) Concrete shall be cured for not less than 10 days.
 - ix) Mechanical needle vibrators shall be used for compaction of concrete.

Signature of Bidder

5 TESTS AND INSPECTION

- i) Testing of concrete for compressive strength shall be done as per IS 516:1959.
- ii) Before despatch, the Engineer-in-charge will inspect the equipment at the maker's works.

6 DOCUMENTATION, WARRANTY AND TRAINING

- i) Detailed shop drawings are to be submitted by the contractor for approval not later than 21 calendar days after the award of work.
- ii) On completion the contractor shall hand over three copies of the O&M manuals.
- iii) The contractor shall guarantee the whole installation for 12 months after handing over against faulty design, materials and workmanship.
- iv) Operation and routine maintenance training shall be given by the contractor to the Department's operators.

BILL OF QUANTITIES

Sl. No. | Description | Unit | Qty

1 | RCC M30 in superstructure | cum | 420

2 | TMT reinforcement Fe 500D | MT | 58

APPROVED MAKES OF MATERIALS

Cement: UltraTech / ACC / Ambuja; Steel: SAIL / TATA / JSW

Note: In case of any discrepancy between drawings and specifications, the decision of the Engineer-in-charge shall be final.

Note: Quantities are approximate and may vary during execution.

Signature of Bidder

Page 3 of 4

Signature of Bidder with seal
Executive Engineer

Signature of Bidder
Page 4 of 4